

DATE: May 4, 2017

TO: ALL BIDDERS OF RECORD

PROJECT NAME: A New Visitor's Pressbox for:  
Cartersville High School

PROJECT NUMBER: 17-008

FROM: KRH Architects  
855 Abutment Road  
Suite 4  
Dalton, GA 30721

PRIME BIDDERS ACKNOWLEDGE THE RECEIPT OF THIS ADDENDUM BY INSERTING THE NUMBER AND DATE IN THE APPROPRIATE POSITION ON THE PROPOSAL FORM. FAILURE TO DO SO MAY SUBJECT THE BIDDER TO DISQUALIFICATION. THIS ADDENDUM IS A PART OF THE CONTRACT DOCUMENTS. IT MODIFIES THEM AS FOLLOWS:

---

**Item No. 1****Section 04200**

Section 04200 - Unit Masonry

Modify this spec section as follows: Delete note #6 under 2.4, A. regarding brick allowance. Face brick for this project shall be: Pine Hall Brick Wirecut F/R Modular.

**Item No. 2****Sheet A1.1**

Add the following notes to the Site Plan: "Any grassing or sod disturbed by construction must be restored to a condition equal to or better than the remainder of the practice field."

"Provide personnel gates as required for access to the sand pit."

**Item No. 3****General**

Statement of Special Inspections

Add this section in its entirety (see attachment).

**Item No. 4****General**

A portion of the existing steel extensions for the bleacher seating must be cut vertically plumb along the perimeter of our new construction to maintain the 2" gap required per details 2 and 4 on sheet A1.2. Do not torch the steel.

**Item No. 5**

See the attached Pre-proposal Meeting Sign-In Sheet.

**Item No. 6****Answers to Contractor's Questions**

1. Detail 1 on A1.2 has a note for 4" split face CMU towards the base of the column, but I do not see it referenced anywhere else to give a height. Is this a correct notation?

(That note should be changed to read "face brick". There is no 4" split face CMU block present on this project.)

2. Per the wall sections and specs the wall assembly will be: Metal studs with batt insulation, DensGlass Gold, Dryvit, Rigid insulation board, Brick - In that order. Is this correct?

(Yes. See Section 09250 Sheathing for the DensGlass Gold, Section 07240 Dampproofing for the Dryvit Backstop NT, Section 04200 for the Rigid Insulation Board and Brick as addressed by this addendum.)

**END OF ADDENDUM**